BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT38906

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/18/2019-20, Date: 16.11.2019

Construction of Additional Hall on ward office building and imptovements of roas and drains at Kodigehalli ward no 08

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of GANGULU REDDY A ( )		
				In Figures		In Words
1	382.49	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specifications.	Cum	1150.0	439863.50	Rupees One Thousand One Hundred Fifty Only
2	319.67	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. specification.	Cum	500.0	159835.00	Rupees Five Hundred Only
3	286.86	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5600.0	1606416.00	Rupees Five Thousand Six Hundred Only
4	286.86	Construction of un-reinforced plain cement concrete pavement, using grade concrete M30 over a prepared base with OPC course aggregate at 0.69 cum fine aggregates at 0.46 cum course and fine aggregtes confirming to IS : 383-2016, with superplastisiser @3lts confirming to IS9103-1999 mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. (with OPC 320Kg per cum GGBS 40 Kg/cum confirming to IS: 12089 course aggregate @ 0.69cum and fine aggregate @ 0.46cum	Cum	5200.0	1491672.00	Rupees Five Thousand Two Hundred Only
5	540	Removing and refixing stone slabs of drains and pointing in CM (1:3)	Sqm	180.0	97200.00	Rupees One Hundred Eighty Only
6	54	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete	Sqm	750.0	40500.00	Rupees Seven Hundred Fifty Only
7	320	KSRB 5-14 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications.	Sqm	1000.0	320000.00	Rupees One Thousand Only

A. Ganguly Reddy

Signature of the contractor

30/04

Executive Engineer

30/04

	Approved Qty.	Description	Unit	Approved Tender Rates of GANGULU REDDY A ( )		
				In Figures		In Words
8	72.7	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5800.0	421660.00	Rupees Five Thousand Eight Hundred Only
9	406.8	Providing and fixing RCC precast cover slab of 100mm thick of drain in cment concrete M20 using graded jelly 20 mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides, transportation, loading unloading, etc.,complete as per the direction of engineer in charge.	Sqm	2500.0	1017000.00	Rupees Two Thousand Five Hundred Only

A Gangulu Reddy

Signature of the Contractor

30/04

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

30/04